



& GIFT SHOPPE
1080 HICKSVILLE RD., SEAFORD NY 11783
(516) 799-8917 www.amishcraftbarn.com

STANDARD SHED:

- Vinyl and wood sheds are standard with two white frame double hung windows w/shutters
- Vents
- Tar Paper on Roof, Architectural shingles are standard
- 25 year roof shingles
- 4x4 Pressure treated foundation runners
- Aluminum Drip Edge
- Roof, floor, wall joists are all 2x4's, 16" on center for maximum strength
- Exterior siding is 1 / 2" Smartside Silverside is plywood siding and has a tough natural looking surface. It has silver tech on inside to keep the shed cooler. It will not split or crack. Resists dents and damage. Keeps its paint up to twice as long as regular siding.
- Floor is 5/8" exterior plywood.
- Double Doors are total 4' wide by 6' high.

OPTIONS:

- Heavy Duty Ramp, 2 x 6 P/T Construction, with steel angle iron for supports
 - 4'x3' \$120
 - 5'x3'\$130
- Flower Boxes- Vinyl Only\$50 ea/\$100pair
- Cupola..... Vinyl Only.....\$ 280
- Shutters ,,.....\$ 30/pair
- Pressure Treated Floor Joists..... Add 4%
- Pressure Treated Plywood Floor 5/8".....Add 5%
- Windows - All windows come standard with screens
 - Upgrade to Oversized Double Hung (18" x 36").\$ 30/each
 - Additional Oversized (18" x 36") DoubleHung.....\$120/each
 - Upgrade to Oversized (24" x 36") Double Hung.....\$45/each
 - Additional Oversized (24" x 36") Double Hung.....\$140/each
- Lofts \$150.00 each for Dutch Barns only

DELIVERY OF YOUR ASSEMBLED SHED:

Must have additional 2' clearance around shed. Must have no overhead obstructions. Trailer must be able to get to at least 20' from where shed is to be dropped. We level up to 4", over that there is additional charge. We supply blocks.

BUILT ON SITE

Site must be clear and relatively level. We level up to 4". We supply blocks for leveling. We must have at least 2' clearance around shed to work.